

INDRAPRASTHA INSTITUTE OF INFORMATION TECHNOLOGY

AMENDMENT TO TENDER NO.IITD/S&P/01/2012-13 FOR SUPPLY, INSTALLATION, TESTING AND COMMISSIONING OF AIRCONDITIONERS AT PERMANENT CAMPUS OF THE INSTITUTE AT OKHLA, NEW DELHI-110020.

Amendment No.1

Changes/modifications have been made under point no.2a, 2a, 3, 4, 5, 6 and 9. Items 7A and 7B have been included. Material for channel under item no.9 has been changed to PVC. Revised format of financial bid is attached. The financial bid is to be submitted only as per revised format.

Amendment No.2

Refer Clause no.6, page 5 (Scope of Work) of Tender Document which may be read as:

“In case of compressor failure no repairs of compressor shall be allowed. The bidder has to provide replacement of compressor from the company. The compressor of AC Tower shall be guaranteed for replacement for 1 year and for rest of the ACs for 5 years free of cost.”

NOTE: All other terms and conditions /Scope of Work remain same.

REVISED FORMAT OF
BILL OF QUANTITIES FOR FINANCIAL / PRICE BID

Particulars	Unit	Qty.	Rate per Unit	Total Amount (all inclusive)
1. Supply, Installation, testing and commissioning of split/window/tower type air conditioning Unit Condensing unit shall be complete with rotary type compressors and air cooled condenser with fan, Evaporator units shall consist of multi rows deep cooling coil with aluminum fins, expansion valves, insulated drain pan, filters, safety controls, cooling thermostat etc. complete within the unit. The enclosure shall be factory painted to a smooth finish. Quoted price shall be including of all necessary, internal wiring of air-conditioning remote controller as required. The Compressors shall be having 5 years replacement warranty. Units shall carry BEE ratings as per scope of work and capacity as under. This shall include drilling holes in wall, cutting & finishing as required. Provision of framing, ply work, glass removal and fixing of units.				
a) Supply and installation of 2 TR split AC including all the material required for installation, as mentioned in the Scope of Work	Nos.	35		
b) Supply and installation of 4 TR tower type Split AC (scroll/reciprocating compressor) including all the material required for installation, as mentioned in the Scope of Work complete <u>with duty sharing arrangement.</u> (Timer based change over electric panel)	Nos.	2		
c) Supply and installation of 1.5 TR window AC including all the material required for installation, as mentioned in the Scope of Work	Nos.	4		
d) Supply and installation of 1 TR	Nos.	5		

window AC including all the material required for installation, as mentioned in the Scope of Work				
e)Supply and installation of 1.5 TR split AC including all the material required for installation, as mentioned in the Scope of Work	Nos	Rate only		
2)Extra for Cabling between indoor and outdoor units beyond 4m included in 1 above a)Supply and installation of 3 core 2.5 sq. mm. PVC insulated copper cable, 1.1 KV grade in conduit/casing capping, Make: Havells, Finolex, Poly Cap. b) –do – for 3core 4 sqmm or as per manufacturer requirements /instructions	Mtrs Mtrs.	Rate Only Rate only		
3)Extra for Supply and installation of one pair (set) of copper tubing along with insulation for 2 TR AC beyond minimum 4 meter included in 1.	Per m.	Rate Only		
4) Extra for Supply and installation of one pair (set) of copper tubing along with insulation for 4 TR AC in beyond minimum 4 meter included in 1 .	Per m.	Rate Only		
5)Extra for Supply and installation of one pair (set) of copper tubing along with insulation for 1.5 TR AC beyond 4 meter included in 1.	Per m.	Rate Only		
6)Supply and Installation of Hard PVC drain piping of suitable dia beyond 4 meter included in 1.	Per m	Rate Only		
7)Supply and installation of 20/32 Amps. DPMCB. Make: ABB/ Le grand /Schneider/Hager 7A- S.I.T.C. of Starter Type Modular Switch Outlets Assembly With Cover Plate for Item 1a.Make MDS/North West /approved equivalent 7B- S.I.T.C. of TPN MCB Of Suitable Capacity With Enclosure For Item 1b Make: ABB/ Le grand /Schneider/Hager	Nos	Rate Only 35 2		
8)MS steel stand for suspending outdoor units from wall /ceiling as required duly primed and painted complete with anchoring arrangement to wall/ceiling/RCC as required.	Nos	37		

9)Provision of PVC channel with cover complete to conceal the piping/wiring, as required	Mtr.	Rate Only		
--	------	-----------	--	--

All Inclusive Total Amount

In figures :

In words :

(Signature with seal of the authorized official)

Date: